

Contractor's Bid Sheet
ORCHARD STREET IMPROVEMENTS PHASE 1
Village of West Manchester
Preble County, Ohio

Contractor: _____

 Date: _____

Prepared By:
 Kramer & Associates, LLC
 101 North Barron Street
 Eaton, Ohio 45320

ROADWAY

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
	<i>ITEMS FOR UNIT PRICE BID</i>						
203	Excavation	35	C.Y.				
204	Subgrade Compaction	325	S.Y.				
253	Pavement Repair	30	C.Y.				
304	6" Aggregate Base (Curb)	35	C.Y.				
304	6" Aggregate Base (Pavement)	63	C.Y.				
304	4" Aggregate Base (Sidewalk & Aprons)	15	C.Y.				
304	Gravel Alley Repair	2	C.Y.				
407	Tack Coat @ 0.075 gal/S.Y.	95	GAL.				
448	Asphalt Concrete Surface Course, Type 1, Medium, Pg 64-22 (Avg. 1 1/4")	55	C.Y.				
448	Asphalt Concrete Intermediate Course, Type 2, Medium, Pg 64-22, (Avg. 1 3/4")	75	C.Y.				
448	Asphalt Wedging, Type 2, Medium, Pg 64-22	25	C.Y.				
603	4" Storm (Downspout Drain) Type E	100	L.F.				
608	Concrete Drive Apron 8"	30	S.Y.				
608	Concrete Walk (4" Mainline)	730	S.F.				
608	Concrete Curb Ramp	2	EACH				
609	Combined Curb and Gutter	620	L.F.				
Spec	Audio/Video Recording of Construction Corridor	1	LUMP				

TOTAL:

TOTAL WRITTEN IN WORDS:

Contractor's Bid Sheet
ORCHARD STREET IMPROVEMENTS PHASE 1
Village of West Manchester
Preble County, Ohio

ADD ALTERNATE 1

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
604	Inlet Reconstruction, Type 2-2B	2	EACH				

TOTAL:

TOTAL WRITTEN IN WORDS: