

**Contractor's Bid Sheet**  
**CUMBERLAND STREET IMPROVEMENTS PHASE 3**  
**Village of Lewisburg**  
**Preble County, Ohio**

Prepared By:  
 Kramer & Associates, LLC  
 101 North Barron Street  
 Eaton, Ohio 45320

Contractor: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

Date: \_\_\_\_\_

**ROADWAY**

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
<b>ITEMS FOR UNIT PRICE BID</b>							
203	Excavation, Including Embankment	750	C.Y.				
203	Excavation, Not Incl. Embkmt. (Subbase Failures)	20	C.Y.				
203	Borrow, as per plan (used as Embankment)	100	C.Y.				
203	Rock Excavation	50	C.Y.				
204	Subgrade Compaction	2,495	S.Y.				
253	Pavement Repair	20	C.Y.				
254	Pavement Planing, Asphalt	500	S.Y.				
301	Bituminous Aggregate Base	132	C.Y.				
304	4" Compacted Aggregate Base (Walks & Drives)	110	C.Y.				
304	6" Compacted Aggregate Base (Curbs)	95	C.Y.				
304	Compacted Aggregate Base (Street)	263	C.Y.				
304	Compacted Aggregate Base (Subbase Failures)	20	C.Y.				
304	Gravel Drive Repair, as per plan	52	C.Y.				
407	Tack Coat @ 0.075 gal./S.Y.	71	GAL.				
448	Asphalt Wedge, as per plan, Type 1 PG 64-22	50	C.Y.				
448	Asphalt Drive Repair, as per plan, Type 1 PG 64-22	6	C.Y.				
448	3" Asphalt Conc. Surface Course, Type 1 PG 64-22	80	C.Y.				
452	Concrete Drive Repair, as per plan	143	S.Y.				
452	Concrete Drive Apron 6" (Residential), as per plan	166	S.Y.				
603	4" Storm (Downspout Drain) Type E	200	L.F.				
603	6" Storm Sewer HDPE, as per plan, in Lawn (Labor and Additional Material, No Pipe)	45	L.F.				
603	12" Storm Sewer HDPE, as per plan, in Street (Labor and Additional Material, No Pipe)	37	L.F.				
603	12" Storm Sewer RCP CL-IV, as per plan, in Street (Labor and Additional Material, No Pipe)	10	L.F.				

**Contractor's Bid Sheet**  
**CUMBERLAND STREET IMPROVEMENTS PHASE 3**  
**Village of Lewisburg**  
**Preble County, Ohio**

Prepared By:  
 Kramer & Associates, LLC  
 101 North Barron Street  
 Eaton, Ohio 45320

**ROADWAY (CONTINUED FROM PAGE 1)**

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
603	12" Storm Sewer RCP CL-IV, as per plan, in Lawn (Labor and Additional Material, No Pipe)	200	L.F.				
604	Type 'D' Storm Inlet, as per plan	5	EACH				
604	Type 'Y' Storm Inlet, as per plan	1	EACH				
604	Reconstruct Storm Inlet, as per plan	4	EACH				
604	Reconstruct/Adjust Manhole to Grade	3	EACH				
608	Curb Ramp	5	EACH				
608	Concrete Walk 4", 5' Walk (Residential Mainline)	6,751	S.F.				
608	Concrete Walk 6", 5' Walk (Residential Drives)	605	S.F.				
609	Curb & Gutter, as per plan	1,706	L.F.				
614	Maintenance of Traffic	1	LUMP				
Spec	Audio/Video Recording of Construction Corridor	1	LUMP				

**TOTAL:**

**TOTAL WRITTEN IN WORDS:**

**MBE SUPPLIER**

ITEM	DESCRIPTION	QUANTITY	UNIT	MATERIALS	LABOR	TOTAL	TOTAL PRICE
<b>ITEMS FOR UNIT PRICE BID (Pipe Only)</b>							
603	6" Storm Sewer HDPE (Pipe Only)	45	L.F.				
603	12" Storm Sewer HDPE (Pipe Only)	37	L.F.				
603	12" Storm Sewer RCP CL-IV (Pipe Only)	210	L.F.				

**TOTAL:**

**TOTAL WRITTEN IN WORDS:**